


# Inverters



Xantrex Power Panel

## Xantrex

### Xantrex Power Panels

Power Panels are packaged power systems built by Xantrex. Power Panels include inverters and are assembled with components specified by the customer.

Features include: One or two SW or DR inverters, powder coated steel back-plate pre-wired to meet all NEC/UL requirements. Single or dual C Series charge controllers may be added. Flexible conduit for connection of the system to the battery enclosure, and 60 amp AC system bypass that allows inverter servicing while keeping AC loads connected to the grid or generator are included. Power Panels are designed for indoor installation only. Standard warranties apply to inverters and controllers installed on Power Panels. Power Panels are built to UL and CSA standards.

Model	DC Voltage Input	Continuous Power Watts	Charger Current Amps	AC Volts Output	Dimensions LxWxH (back plate) in.	Weight (lbs)	MSRP
PP-SW5548S	48	5500	75	120VAC 60 Hz	40 x 43 x 1	248	\$5,150.00
PP-SW5548D	48	11,000	75 x 2	120/240VAC 60Hz	40 x 43 x 1	396	\$8,905.00
PP-SW4024S	24	4000	120	120VAC 60Hz	40 x 43 x 1	217	\$4,250.00
PP-SW4024D	24	8000	120 x 2	120/240VAC 60Hz	40 x 43 x 1	334	\$7,505.00
PP-SW4048S	48	4000	60	120VAC 60 Hz	40 x 43 x 1	217	\$4,250.00
PP-SW4048D	48	8000	60 x 2	120/240VAC 60 Hz	40 x 43 x 1	334	\$7,647.00
<b>OPTIONS</b>							
PPO-C40	C40 DC charge or load or diversion controller, installed complete with prewired 60 amp DC breaker						\$258.00
PPO-DVM/C40	Accumulating amp hour meter with LCD display, installed on the front of the C40						\$99.00
PPO-CD15	15 amp DC load breaker, prewired and installed in the DC disconnect						\$59.00
PPO-CD20	20 amp DC load breaker, prewired and installed in the DC disconnect						\$59.00
PPO-CD60	60 amp DC load breaker, prewired and installed in the DC disconnect						\$59.00